

WHARRAM BUILT Ltd.

Professionally built Wharram catamarans

www.wharram.com

Greenbank Road
Devoran
Truro
Cornwall
TR3 6PJ

Tel: +44 (0) 1872 864 792

Fax: +44 (0) 1872 864 791

Email: wharram@wharram.com

Mana 24 kit - Price list - July 2017

Cost of complete kit *£10,665.00

*All prices excluding VAT, excluding shipping costs (shipped FOD, Freight on Delivery)

1. Boatbuilding Kit, total cost £8,020.00

- Complete set of plywood parts to build two hulls, crossbeams and motorbox, CNC precision cut. All plywood Robbins Elite BS1088 Marine Plywood, guaranteed for 15 years, manufactured from selected Gaboon (Okoume) veneers throughout.

All hull parts are epoxy coated on the inner surface, most interior parts on both surfaces. Parts for crossbeams are epoxy glassed on the inside surfaces. These smooth/glossy epoxy coated inner surfaces will need a light sanding and a second coat of epoxy, applied after assembly.

- Platform panels, 2 large, 2 small, prefabricated from 40mm plastic honeycomb, glassed top and bottom.
- Small hardwood timber parts, CNC cut to size, ready for final shaping, sanding and fitting.
- Perspex windows and washboards, CNC precision cut.
- WEST Epoxy kit, includes all resins, pumps, fillers and glass cloth, mixing sticks, 1 box vinyl gloves, 1 rubber squeegee.
- Sikaflex 295 for fitting windows.
Sikaflex 221 for bedding fittings etc.
Neoprene rubber for sealing hatches.
Rubber for padding beam mounts.
Gripfast nails, stainless steel machine screws, cable-ties and roller-sleeves (to be cut into paint/epoxy-pads), 2 paint-pad handles.
- Douglas Fir timber for stringers, framing etc. and hardwood for hatch coamings (mahogany) and keel strips (iroko), all in long lengths to be cut to size by builder.*

*N.B. For overseas customers **Boatbuilding Kit** can be bought excluding the long lengths of Douglas Fir and hardwood timber for easier transport. Cost deducted by £535.

WHARRAM BUILT Ltd.

Professionally built Wharram catamarans

www.wharram.com

Greenbank Road
Devoran
Truro
Cornwall
TR3 6PJ

Tel: +44 (0) 1872 864 792

Fax: +44 (0) 1872 864 791

Email: wharram@wharram.com

Mana 24 kit

Price list, continued

2. Blocks, fittings and rope kit, total cost £985

- All blocks, cleats, shackles and other fittings to rig the Mana
- All ropes for sheets, halyards and standing rigging (Dyneema).
- Stainless steel buckles and webbing straps for crossbeams.
- Shockcord for tillers and hatches.
- Aluminium boathook/mizzen boom.
- Set of fittings for both mastheads and hinging unit for base of main mast, fabricated from aluminium and stainless steel.

3. Masts, total cost £ 315

- Aluminium mast tubes.
4 ½" OD x 10swg for main mast, 2 pieces @ 5m and 2.30 long, plus sleeve.
3" OD x 10swg for mizzen, 4m long.

4. Sails, made by Jeckells of Wroxham, total cost £1,345 – specify colour

- Mainsail with two reefs
- Mizzen with 1 reef

WHARRAM BUILT Ltd.

Professionally built Wharram catamarans

www.wharram.com

Greenbank Road
Devoran
Truro
Cornwall
TR3 6PJ

Tel: +44 (0) 1872 864 792

Fax: +44 (0) 1872 864 791

Email: wharram@wharram.com

Mana 24

Building time estimate:

We kept precise building hours while building the prototype. We built to a high quality standard with excellent finish, i.e. a lot of time spent on precision sanding, fairing etc. Building time in the early stages of building is greatly reduced by the CNC cut plywood parts, which takes away all the worry of measuring and cutting and lets the builder assemble the hulls very quickly.

We supply the ply parts pre-coated with epoxy on the inner surfaces, which cuts down on a lot of coating and sanding time before one is able to assemble. The single epoxy coat is very flat and needs only a light sanding to prepare it for a second coat, which is applied later after the parts are joined together.

Summing up of the times we took:

All construction work; hulls, beams, gaffs, tillers, hatches, including epoxy coating all interior surfaces: approx. 500 hours

All exterior glassing work; hulls and crossbeams: 90 hours

All sanding of glassed surfaces: 45 hours

Painting, two coats epoxy primer, two coats 2-pack topcoat incl. non-slip decks and antifouling: approx. 80 hours.

N.B. What should be noted is how many hours it takes to do sanding and painting compared to the building time. Glassing, sanding, fairing and painting add up to 30% of the total building time. On our basic building time estimates in our Design Book, final finishing and painting are not taken into account. Working from a kit does save many hours.

Transport sizes and weights:

- The plywood kit, including made-up platform panels will be in labeled bagged bundles measuring in total approx. 2.5m x 1.20m x 0.3m and weighs around 300kg.
- Fastenings, blocks, fittings and ropes, 1 box, approx. 60 x 40 x 30cm. Weight 25kg.
- The WEST epoxy kit measures approx. 1.3m x 0.6m x 0.45m and weighs around 100kg.

(For overseas transport the above items have to be packaged in one special wooden pallet crate - 2.62m x 1.29m x 0.77m - at additional cost of £180. Epoxy resins/hardener will be supplied through a local dealer, as these are hazardous products and expensive to transport).

- Timber will be a long parcel (around 3.5m - 4m long) and will weigh around 50-60kg.
- Aluminium masts, in max. 5m long sections, weight incl. fittings 40kg
(For overseas customers we advise them to source the timber and masts locally).

You will be able to collect the complete kit from Cornwall yourself on a trailer or in a van saving on a lot of shipping cost and paperwork.